

West Side Storm Sewer Study Status Update

August 25, 2014








Work Completed To Date

- Survey of Storm Sewer System
 - >1,500 Structures







Work Completed To Date

- Flow monitoring capturing storm events
 - Multiple locations, data is used for calibration of storm sewer model












Work Completed To Date

- Compilation of Resident Information
 - Questionnaires/Surveys
 - Resident information
 - Open house
 - Photographs
 - Videos
 - Field visits









Hydrologic and Hydraulic Modeling

- Model development
 - Incremental approach to develop a plan
 - Comprehensive analysis
 - Identify underutilized segments and/or restrictions
 - Identify potential improvements
- Calibration from monitoring & flood events
 - April 2013, May 2014 and June 2014







Model Calibration Results

Kenilworth Gardens (April 2013)

Debris at High Water Mark






Storm sewer system has 2-yr capacity







Model Calibration Results



Wilshire (April 2013)



Storm sewer system has 2-yr capacity








Model Calibration Results

Valley View/Kilpatrick (April 2013)





Storm sewer system has 2-yr capacity







Next Steps


- Finalize existing model
- Evaluate proposed drainage improvements
 - Green infrastructure
 - Rain gardens
 - Green islands
 - Bio-swales
 - Stormwater conveyance
 - Storm sewers
 - Pump station
 - Stormwater storage
 - Open space limitations
 - Coordination with other municipalities














Limitations of Existing System





Next Steps

- Desired level of protection Need input
 - Protection of homes and structures is most important
 - Is street ponding acceptable?
 - A certain design event? (5-yr, 10-yr, 50-yr, 100-yr, etc.)
 - New developments
 - Storm sewers designed for a 10-yr event
 - Runoff excess of the 10-yr storm is conveyed overland to a storage area
- How would the proposed plan handle the April 2013 storm event?







End of Presentation

Questions



